


BRUHAT BANGALORE MAHANAGARA PALIKE


MODIFIED APPROVED SCHEDULE - B

Name of the work:- Providing chain link fencing in Sanjeevininagara and Gundajanaya temple opp. Govt. Land in ward no. 07 Byatarayanapura, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Quotation Rates of	
				Sambashiva	
				In Figures	In Words
1	2640.56	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1 (a) /2.3.5 (Page No. 5 & Item No. 2.3)	Cum	171.05	Rupees One Hundred Seventy One and Five Paise Only
2	4.14	KSRRB 2900-4.1: Providing and laying in position plain cement concrete mix 1:4:8 with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Page.12 & Item No. 4.3)	Cum	4709.71	Rupees Four Thousand Seven Hundred Nine and Seventy One Paise Only
3	9.32	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (Page No. 12 & Item No. 4.6).	Cum	3836.16	Rupees Three Thousand Eight Hundred Thirty Six and Sixteen Paise Only
4	9.32	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2014-15	Cum	4542.48	Rupees Four Thousand Five Hundred Forty Two and Forty Eight Paise Only
5	9.16	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2014-15	Cum	5176.69	Rupees Five Thousand One Hundred Seventy Six and Sixty Nine Paise Only
6	80.50	Supplying and fixing M. S. Rectangular Poles made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms, including cost of all materials, cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead and lift and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earth work and concrete) (Page No. 231 & Item No. 37.2 PWD SR 20014-15).	Rmtr	1082.98	Rupees One Thousand Eighty Two and Ninety Eight Paise Only

7	148.00	Providing and fixing M. S. Block Pipe of 38 mm dia, of heavy guage of 1:4, including removing the bends, cutting the pipe in between the two verticle poles (M. S. Rectangular Poles) and spot welding the chain link with M. S. Block Pipe, including cost of all materials, wastage in cutting and scaffolding wherever necessary, with all lead and lift as directed by the Engineer-in-charge of the work etc., complete including 2 coats of approved quality paint over one coat of shop painting (Page No. 231 & Item No. 37.4 PWD SR 2014-15	Rmtr	313.77	Rupees Three Hundred Thirteen and Seventy Seven Paise Only
8	111.00	Providing Chain Link Fencing 50 mm size of 8 guage property striched between rectangular poles and fixed with suitable bolts and nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required, including cost of all materials, labour, lead and lifts, cutting, bending scaffolding wherever necessary, wastage and lapping etc., complete as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (Page No. 231 & Item No. 37.3 PWD SR 2014-15	Sqm	663.22	Rupees Six Hundred Sixty Three and Twenty Two Paise Only
9	2640.56	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	Cum	66.65	Rupees Sixty Six and Sixty Five Paise Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92